

CORRECTED BID RESPONSE FORM FOR LABOR
 UPDATED QUANTITIES
 9/14/2022

| ITEM NO. | SPEC PAYMENT REFER | ITEM | EST. QTY. | UNIT | UNIT PRICE | TOTAL AMOUNT |
|-------------|--------------------|--|-----------|------|------------|--------------|
| 1.00 | | Backbone and Distribution Duct Installation | | | | |
| 1.01 | Exhibit A | Directional Bore One (1) – 1.25" HDPE duct (SDR 11 at 36" minimum depth) with restoration | 49,402 | LF | \$ | \$ |
| 1.02 | Exhibit A | Directional Bore Two (2) – 1.25" HDPE ducts (SDR 11 at 36" minimum depth) with restoration | 6,954 | LF | \$ | \$ |
| 1.03 | Exhibit A | Directional Bore Three (3) – 1.25" HDPE ducts (SDR 11 at 36" minimum depth) with restoration | 547 | LF | \$ | \$ |
| 2.00 | | Handhole Placement | | | | |
| 2.01 | Exhibit A | 30"x60"x30" deep traffic rated split lid handhole in grass with restoration | 25 | EA | \$ | \$ |
| 2.02 | Exhibit A | 30"x48"x24" deep traffic rated split lid handhole in grass with restoration | 19 | EA | \$ | \$ |
| 2.03 | Exhibit A | 17"x30"x24" deep non-traffic rated handhole in grass with restoration | 151 | EA | \$ | \$ |
| 2.04 | Exhibit A | 14"x19"x12" HDPE Light Duty handhole | 292 | EA | \$ | \$ |
| 3.00 | | Backbone and Distribution Cable Placement | | | | |
| 3.01 | Exhibit A | Place fiber optic cable in HDPE Ducts | 25,483 | LF | \$ | \$ |
| 4.00 | | MST Installation | | | | |
| 4.01 | Exhibit A | 6 Port MST – any tail length | 176 | EA | \$ | \$ |
| 4.02 | Exhibit A | 6 Port MST - 100' tail | 11 | EA | \$ | \$ |
| 4.03 | Exhibit A | 6 Port MST - 250' tail | 22 | EA | \$ | \$ |
| 4.04 | Exhibit A | 6 Port MST - 500' tail | 44 | EA | \$ | \$ |
| 4.05 | Exhibit A | 6 Port MST - 750' tail | 46 | EA | \$ | \$ |

| | | | | | | |
|-------------|-----------|---|-----|----|----|----|
| 4.06 | Exhibit A | 6 Port MST - 1000' tail | 35 | EA | \$ | \$ |
| 4.07 | Exhibit A | 6 Port MST - 1500' tail | 18 | EA | \$ | \$ |
| 5.00 | | Drop Duct Installation | | | | |
| 5.01 | Exhibit A | Plow, trench, or bore one (1) .75" HDPE with restoration | | LF | \$ | \$ |
| 5.02 | Exhibit A | Plow, trench, or bore one (1) .75" HDPE with restoration per instance (up to 100ft) | 345 | EA | | |
| 6.00 | | Drop Cable Installation – Standard APC SC Single End to Stub | | | | |
| 6.01 | Exhibit A | Any drop cable length up to 1,000' | 345 | EA | \$ | \$ |
| 6.02 | Exhibit A | 100' Drop cable | 35 | EA | | |
| 6.03 | Exhibit A | 150' Drop cable | 117 | EA | \$ | \$ |
| 6.04 | Exhibit A | 200' Drop cable | 212 | EA | \$ | \$ |
| 6.05 | Exhibit A | 250' Drop cable | 117 | EA | \$ | \$ |
| 6.06 | Exhibit A | 300' Drop cable | 148 | EA | \$ | \$ |
| 6.07 | Exhibit A | 500' Drop cable | 117 | EA | \$ | \$ |
| 6.08 | Exhibit A | 750' Drop cable | 41 | EA | \$ | \$ |
| 6.09 | Exhibit A | 1,000' Drop | 20 | EA | \$ | \$ |
| 7.00 | | Customer Premise Installation | | | | |
| 7.01 | Exhibit A | Enclosure Installation (on outside of structure) | 345 | EA | \$ | \$ |
| 7.02 | Exhibit A | Install Customer Premise Equipment (CPE) | 345 | EA | \$ | \$ |
| 8.00 | | Marker Post Installation | | | | |
| 8.01 | Exhibit A | Install Standard Marker Post | 50 | EA | \$ | \$ |
| 8.02 | Exhibit A | Install Test Station Marker Post | 19 | EA | \$ | \$ |

TOTAL BID PRICE _____